

THE PROPERTY OF THE PROPERTY O

MR ROCORY RESOLUTION 1985

FP0 8431 0.2



SELECTE JUN 1 2 1986

PROJECT DOCUMENTATION REPORT

FORACS TARGET
SSRNM ARRAY INSTALLATION
AUTEC/St. Croix

November 1984

FPO-1-84(31)

AD-A168 657



CHESAPEAKE DIVISION
NAVAL FACILITIES ENGINEERING COMMAND
WASHINGTON NAVY YARD
WASHINGTON, DC 20374

Approved for public release;
Distribution Unlimited

THE FILE COPY

86 6 12 00





PROJECT DOCUMENTATION REPORT

FORACS TARGET SSRNM ARRAY INSTALLATION AUTEC/St. Croix

November 1984

FPO-1-84(31)

Prepared by: Lawrence Mendlow Bruce Schuckman Sandra Vickstrom

Approved:

D. A. Raecke, Director

Construction Division

E. B. Spencer, Technical Director Ocean Engineering and Construction Project Office

DISTRIBUTION STATEMENT A Approved for public releases Distribution Unlimited

A A	
Unclassified	AN AUGUMA
SECURITY CLASSIFICATION OF THIS PAGE	AD-1168657
REPORT DOCUMENT la. REPORT SECURITY CLASSIFICATION	
Unclassified	1b. RESTRICTIVE MARKINGS
2a. SECURITY CLASSIFICATION AUTHORITY	 DISTRIBUTION AVAILABILITY OF REI Approved for public release; distribution is unlimited
2b. DECLASSIFICATION/DOWNGRADING SCHEDULE	
4. PERFORMING ORGANIZATION REPORT NUMBER FPO-1-84(31)	5. MONITORING ORGANIZATION REPORT
6a. NAME OF PERFORM. ORG. 6b. OFFICE SYM Ocean Engineering & Construction Project Office CHESNAVFACENGCOM	7a. NAME OF MONITORING ORGANIZATION
6c. ADDRESS (City, State, and Zip Code) BLDG. 212, Washington Navy Yard Washington, D.C. 20374-2121	7b. ADDRESS (City, State, and Zip
8a. NAME OF FUNDING ORG. 8b. OFFICE SYM	9. PROCUREMENT INSTRUMENT INDENT
8c. ADDRESS (City, State & Zip)	10. SOURCE OF FUNDING NUMBERS PROGRAM PROJECT TASK WORK UN ELEMENT # # ACCESS
11. TITLE (Including Security Classificat FORACS Target SSRNM Array Installation AUReport	
12. PERSONAL AUTHOR(S)	n 17å alandaran
Lawrence Mendlow, Bruce Schuckman & Sandr. 13a. TYPE OF REPORT 13b. TIME COVERED	14. DATE OF REP. (YYMMDD) 15. PAGE
FROM TO	84-11 18
16. SUPPLEMENTARY NOTATION	
FIELD GROUP SUB-GROUP FORAC	CT TERMS (Continue on reverse if net S. Arrays, Atlantic Undersea Test ar ation Center, St. Croix
19. ABSTRACT (Continue on reverse if nece NOSC Code 6362 tasked CHESDIV FPO-1 to in Andros Island, Bahamas and one FORACS Tar Underwater Tracking Range, St. Croix, USV	stall two FORACS Targets at AUTEC, get and one SSRNM Array at the
20. DISTRIBUTION/AVAILABILITY OF ABSTRACT SAME AS RPT.	21. ABSTRACT SECURITY CLASSIFICATION
22a. NAME OF RESPONSIBLE INDIVIDUAL Jacqueline B. Riley	22b. TELEPHONE 22c. OFFICE SYMBO 202-433-3881
DD FORM 1473, 84MAR	SECURITY CLASSIFICATION OF THIS PAGE

TABLE OF CONTENTS

A 3

List of Tables	iii
List of Figures	iii
List of Acronyms	iv
1.0 Management Summary	1
1.1 Background	1
1.2 System Description - FORACS	
1.3 System Description - SSRNM	1 3 3 3 5
1.4 Construction Site - AUTEC	3
1.5 Construction Site - St. Croix	3
1.6 Construction Planning Summary	5
1.7 Construction Operations Summary	5
2.0 Location Details	7
2.1 Geographical Data, Site Plan, and System Element	
Locations	7
3.0 Installation Details	7
3.1 Installation Details/Comparison with Specifications	7
4.0 Recommendations for Future SSRNM Installations	11

Accesio	n For		
NTIS	CRA&I	2	
DTIC	TAB]
Unanno	unced		3
Justific	ation		
By Distribu	ition/		
A.	vailabilit	y Cod€	es .
Dist		and for ecial	
A-1			



LIST OF TABLES

8

۷.۷	St. Croix installed Locations	10
	LIST OF FIGURES	
1.1	FORACS Target	2
1.2	SSRNM Array	4
2.1	AUTEC Installations	9
2.2	St. Croix Installations	11
3.1	SSRNM Termination Device	13

2.1 AUTEC Installed Locations

LIST OF ACRONYMS

CHESDIV Chesapeake Division, Naval Facilities

Engineering Command.

NOSC Naval Ocean Systems Center.

UCT-1 Underwater Construction Team One.

APL Applied Physics Laboratory, University

of Washington.

AUTEC Atlantic Underwater Test and Evaluation

Center.

AFWTF Atlantic Fleet Weapons Training

Facility.

UTR St. Croix Underwater Tracking Range.

DTNSRDC David W. Taylor Naval Ship Research and

Development Center.

SUPSALV Supervisor of Salvage, Naval Sea

Systems Command.

BIW Boston Insulated Wire Company.

FORACS Fleet Operational Readiness Accuracy

Check Site.

SSRNM Surface Ship Radiated Noise Measurement.

1.0 MANAGEMENT SUMMARY

1.1 Background

deddd Chwyraeth, Labarriau - garrenna

STATE A TOTAL OF THE SECOND OF

NOSC Code 6362 tasked CHESDIV FPO-1 to install two FORACS Targets at AUTEC, Andros Island, Bahamas and one FORACS Target and one SSRNM Array at the Underwater Tracking Range, St. Croix, USVI. The organizations that participated in the project were:

- 1) NOSC Funding, SSRNM Equipment and ET's.
- 2) CHESDIV Installation Planning, Installation Coordination, SEACON.
- 3) UCT-1 Deckforce, Installation Planning.
- 4) APL FORACS Equipment and Engineers, FORACS Targets Positions.
- 5) AUTEC On-site Logistics.
- 6) AFWTF On-site Logistics.


NOSC funded the project through the following documents:

N66001	83 W R	00412	\$30,000.00	23	JUN	1983
N66001	83RC	00097	\$100,000.00	10	AUG	1983
N66001	84WR	00086	\$10,000.00	4	NOV	1983
N66001	84WR	00214	\$137,000.00	19	JAN	1984
N66001	84RC	00053	\$78,000.00	8	FEB	1984
N66001	84WR	00391	\$45,000.00	23	APR	1984
N66001	84WR	00491(Amend	1) \$4,000.00	22	MAY	1984
N66001	84RC	00094	\$32,000.00	22	MAY	1984

1.2 System Description - FORACS

FORACS ranges consist of a series of radar and acoustic targets used to check the accuracy of a ship's sensors. CHESDIV was tasked to install several acoustic targets (a deep and shallow water target at AUTEC and a deep water target at St.Croix with a backup to be installed as a shallow water target at St.Croix if time permitted). See Figure 1.1 for a typical FORACS acoustic target.

Each target is separately cabled back to shore (with Simplex .057/.180 Quad Cable) and into a control panel located in the control room of the appropriate facility. CHESDIV efforts consisted of bringing the cable to the on-shore termination boxes. The connections to the termination boxes and the cabling and connections between the boxes and the control panel were carried out by the facility and APL.



FORACS Target

Figure 1.1

The targets were designed and built by APL. The target locations were selected by APL after consultation with the respective facilities. The position was not considered critical so there was no specification of accuracy in the X-Y plane.

However, depth was considered important and specifications for depth were given; for the shallow targets the depth was permitted to vary from the selected depth to 10 ft deeper than the selected depth. For the deep targets the depth was to be between 1200 and 1300 feet. However this was permitted to be varied on site with the consent of the APL engineer on board.

1.3 System Description - SSRNM

The SSRNM system is a vertical acoustic array designed to analyze the acoustic signature of a surface ship. The SSRNM array consists of a subsurface float, a Kevlar strength member, electrical cables and four hydrophones. The array was also designed to have a powered pinger on it for 3-D location on the range. The array is held in position by a concrete clump (17,000 lbs in air, 9,600 lbs in water). A specially designed cable connects the array to shore, with transformers in a junction chamber at the base of the array to insure proper signal strength/impedance. On shore is an electronics van where all the signal processing occurs. See Figure 1.2 for SSRNM Array.


The array was designed and built by NOSC in conjunction with DTNSRDC. The location was provided by NOSC and the UTR. Once again vertical control was considered more important than horizontal control. Horizontally, a several hundred foot error was considered acceptable, but vertically, the top of the buoy had to be between a depth of 100 ft and 120 ft, based on the draft of large tankers and diver limitations.

1.4 Construction Site - AUTEC

AUTEC is located on Andros Island, Bahamas. It consists of an acoustic range, a weapon range and a FORACS range with all the support facilities to maintain the base, the ranges and all the equipment that the ranges use. The cable landing site was inside a cut in the reef permitting SEACON to approach no closer than 1 mile from shore and necessitated use of an AUTEC LCM-6 to pull the cable to shore. An existing cable trench was used to route the cable from the beach to the Command and Control building.

1.5 Construction Site - St. Croix

The St.Croix UTR under the cognizance of AFWTF, Roosevelt Roads, PR is located at Sprat Hall, 1 mile north of Frederiksted, ST.Croix, USVI.



SSRNM ARRAY

Figure 1.2

The facility overlooks the beach landing site on a steep 30 ft high bluff. The shore drops off fairly quickly, permitting SEACON to approach within 1200 ft of the shore.

1.6 Construction Planning Summary

23 Jun 83	Original	tasking	for	FORACS/SSRNM
	Installat	ion.		

17 Nov 83 Dates of Installation and use of SEACON finalized.

19 Jan 84 Op order 2-84 promulgated.

20 Mar 84 Project Execution Plan - FPO-1-84(1)

promulgated.

20 May 84 Addendum to PEP promulgated.

22 May 84 Op order 3-84 promulgated.

1.7 Construction Operations Summary

13-18 Feb 1984	SEACON	towed	from	Norfolk,	VA	to	Fort
	Lauderd	lale. E	rL.				

19-30 Mar

SEACON and project mobilization at Fort
Lauderdale, FL. The effort included
the assembly of the FORACS structures,
the winding of the electrical cables
and the Kevlar rope onto Pengo reels,
and loading the SSRNM cable in SEACON's
cable tank.

31 Mar - 1 Apr SEACON transited to AUTEC.

2 Apr
CHESDIV personnel setup Miniranger shore stations. UCT-1 and AUTEC personnel set up the beach site for

hauling the cable ashore.

3-4 Apr Installed deep water FORACS Target.

5-6 Apr Installed shallow water FORACS Target.

7 Apr UCT-1 and CHESDIV personnel pulled the near shore portion of the cables into position and demobilized the shore sites. SEACON departed AUTEC.

8-13 Apr The USS PAPAGO, ATF 160, towed SEACON to NAVSTA Roosevelt Roads, PR.

22.24.3	
F(N)	icked up the SSRNM clump and the ORACS cable for St.Croix Operations at AVSTA Roosevelt Roads. Wound the ORACS cable on Pengo reel.
15 Apr SE	EACON transited to St.Croix.
	CT-1 and CHESDIV personnel set up the hore site.
SS th No	lumbed the SSRNM site and cut the SRNM Kevlar strength member to match he depth at the installation site. OSC personnel installed a new socket n the Kevlar strength member.
18 Apr In	nstalled deep & shallow FORACS Targets.
19 Apr Eq	quipment failure caused loss of SSR NM lump/shore cable/junction chambers.
cl	
29 Apr Wi	ith SUPSALV personnel using Deep Drone board USNS MOHAWK, T-ATF 170, the lump was recovered aboard SEACON.
29 Apr Wind all controls and control controls and control	board USNS MOHAWK, T-ATF 170, the
29 Apr Winds and City	board USNS MOHAWK, T-ATF 170, the lump was recovered aboard SEACON.
29 Apr Wind all city and city and city are selected as a city are selected as	board USNS MOHAWK, T-ATF 170, the lump was recovered aboard SEACON. ecovered the shore cable into the EACON's cable tank. CT-1 and CHESDIV personnel broke down he shore site. SEACON transited to
29 Apr Winds C: 30 Apr Res SI May UC th NA 14-18 May Bi bot 23-25 May SE	board USNS MOHAWK, T-ATF 170, the lump was recovered aboard SEACON. ecovered the shore cable into the EACON's cable tank. CT-1 and CHESDIV personnel broke down he shore site. SEACON transited to AVSTA Roosevelt Roads. IW reterminated the SSRNM cable on
29 Apr Winds C: 30 Apr Res SE 1 May UC th NA 14-18 May Bi	board USNS MOHAWK, T-ATF 170, the lump was recovered aboard SEACON. ecovered the shore cable into the EACON's cable tank. CT-1 and CHESDIV personnel broke down he shore site. SEACON transited to AVSTA Roosevelt Roads. IW reterminated the SSRNM cable on oard SEACON. EACON mobilized at NAVSTA Roosevelt
29 Apr Winds C: 30 Apr Re SE 1 May UC 14-18 May Bi 14-18 May Bi 23-25 May SE 25-26	board USNS MOHAWK, T-ATF 170, the lump was recovered aboard SEACON. ecovered the shore cable into the EACON's cable tank. CT-1 and CHESDIV personnel broke down he shore site. SEACON transited to AVSTA Roosevelt Roads. IW reterminated the SSRNM cable on oard SEACON. EACON mobilized at NAVSTA Roosevelt oads.
29 Apr Winds C: 30 Apr Re SE 1 May UC 11 May UC 12 May BI	board USNS MOHAWK, T-ATF 170, the lump was recovered aboard SEACON. ecovered the shore cable into the EACON's cable tank. CT-1 and CHESDIV personnel broke down he shore site. SEACON transited to AVSTA Roosevelt Roads. IW reterminated the SSRNM cable on oard SEACON. EACON mobilized at NAVSTA Roosevelt oads. EACON transited to St.Croix.
29 Apr Winds and Circles 20 Apr Res SE 1 May UC th NA 14-18 May Bi 23-25 May SE 25-26 May SE 26 May SE 27-28 May In SE 27-28 M	board USNS MOHAWK, T-ATF 170, the lump was recovered aboard SEACON. ecovered the shore cable into the EACON's cable tank. CT-1 and CHESDIV personnel broke down he shore site. SEACON transited to AVSTA Roosevelt Roads. IW reterminated the SSRNM cable on oard SEACON. EACON mobilized at NAVSTA Roosevelt oads. EACON transited to St.Croix. et up the shore site.
29 Apr Winds and City	board USNS MOHAWK, T-ATF 170, the lump was recovered aboard SEACON. ecovered the shore cable into the EACON's cable tank. CT-1 and CHESDIV personnel broke down he shore site. SEACON transited to AVSTA Roosevelt Roads. IW reterminated the SSRNM cable on oard SEACON. EACON mobilized at NAVSTA Roosevelt oads. EACON transited to St.Croix. et up the shore site. Installed the SSRNM array.

2.0 LOCATION DETAILS

2.1 Geographical Data, Site Plan & System Element Locations

AUTEC is located at Andros Island Bahamas. The FORACS Range uses a local grid with the North Tower as the origin and the Y axis at an azimuth of 305.9°. CHESDIV chose to use a grid system based on true north and selected on old AUTEC construction grid. In this system the location of the North Tower is (11430 X, 47625 Y). To convert from the FORACS grid to this grid system use the following formulas:

$$X_{CG} = X_f \cos(305.9) - Y_f \sin(305.9) + 11430$$

 $Y_{CG} = X_f \sin(305.9) + Y_f \cos(305.9) + 47625$

To convert from the construction grid to the FORACS grid use the following formulas:

$$X_f = (X_{cg} - 11430) \cos(305.9) + (Y_{cg} - 47625) \sin(305.9)$$

 $Y_f = (X_{cg} - 11430) \sin(305.9) + (Y_{cg} - 47625) \cos(305.9)$

The conversion from latitude/longitude to FORACS grid is done by the range. The North Tower and the Instrument Tower were used as miniranger transponder stations. The location of the miniranger stations and installed targets are shown in Table 2.1 and Figure 2.1.

The St.Croix Underwater Tracking Range is located on the west side of St.Croix, north of Frederiksted. The range uses a local grid based on a rotation and translation of UTM coordinates. This was the system used for this project. Conversion between latitude/longitude and the grid system is accomplished by the range. Sprat Hall and the Coast Guard Light at the foot of Frederiksted Pier were used as miniranger shore transponder sites. The locations of the miniranger sites, the FORACS targets and the SSRNM array system are shown in Table 2.2 and Figure 2.2.

3.0 JSTALLATION DETAILS

3.1 Installation Details/Comparison with Specifications

The FORACS target was a package provided by APL and installation went as planned. No changes in the design were required. However, there was a break in the cable during the installation of the shallow FORACS target at AUTEC. The splice to reconnect the cable is in the cable trench well on shore. What was learned from this experience is that the shallow FORACS targets are diver repairable. By simply removing the bolts from the chamber flange connection and disconnecting the underwater mateable connectors, the chamber can be brought to the surface. All location changes were as a result of water depth requirements and agreed to by APL. A comparison between the planned and the installed locations is shown in Table 2.1.

SITE	PLANNED X (E)	PLANNED LOCATION X (E) Y (N)	CONSTRUCTION GRID INSTALLED LOCATION	CONSTRUCTION GRID NSTALLED LOCATION X	FORACS GRID INSTALLED LOCATION X Y	FORACS GRID ALLED LOCATION Y
NORTH TOWER	11,430	47,625	11,430	47,625	0	0
INSTRUMENT TOWER	13,617	38,159	13,617	38,159	10,882	3,862
DEEP FORACS TARGET	20,675	44,120	20,689	43,461	13,069	2,191
HOLD POINT FOR DEEP LFTS	19,000	40,460	19,360	40,630	14,344	3,228
SHALLOW FORACS TARGET	19,800	41,720	19,629	41,388	13,916	2,945
HOLD POINT FOR SHALLOW LFTS	19,000	40,460	19,167	40,394	14,369	3,310

Ĺ

がない。

250 Jan 250 B20


D

ř

Note: All coordinates are in feet.

AUTEC INSTALLED LOCATIONS

Table 2.1




AUTEC Installations
Figure 2.1

SITE	PLANNED X (E)	LOCATION Y (N)	INSTALLED X	LOCATION Y
SPRAT	61,998	37,859	61,998	37.859
COAST GUARD LIGHT	64,850	28,375	64,850	28,375
DEEP FORACS TARGET	58,302	28,774	58,487	29,521
HOLD POINT FOR DEEP LFTS	60,400	36,975	60,610	36,985
SHALLOW FORACS TARGET	60,334	34,225	60,584	34,311
HOLD POINT FOR SHALLOW LFTS	60,400	36,975	60,722	37,290
HOLD POINT FOR SSRNM ARRAY	60,279	37,333	60,623	37,054
SSRNM ARRAY	52,986	35,029	53,063	35,023

Note: All coordinates are in feet.

ST. CROIX INSTALLED LOCATIONS

Table 2.2



♦ PROPOSED TARGET LOCATION

ACTUAL TARGET LOCATION

MINI-RANGER SHORE STATIONS

St. Croix Installations

Figure 2.2

11


DEPTH IN FATHOMS

The SSRNM array, see Figure 1.2, was changed from the original design due to the following operational and installation considerations:

- A. The original design was based on a 3000 ft water depth, the selected site was only 2700 ft, and required that 300 ft of Kevlar strength member be cut off and the Kevlar reterminated.
- B. The triangular termination device was modified to hold the extra electrical array cable (300 ft) and provide a better strain relief system. See Figure 3.1.
- C. Due to the break in the Kevlar strength member a splice between two Kevlar lengths exists about 100 ft above the clump.
- D. While attempting to install the pinger, the back plate of the support bracket was lost over the side. No spare was available so the pinger was not installed. If needed divers can install a new pinger, but depth capabilities to 200 ft will be required by the divers used because the pinger pigtail came up approximately 50 ft short of the bottom of the buoy and not the 5 ft as planned.
 - E. The double buoy system was welded together as well as bolted.
 - F. The location of the SSRNM is off by 77 ft to the east.
- G. The depth of the top of buoy was measured by diver at 142 ft, 28 ft deeper than measured by the lowering line during the installation. The obvious answer as to why the depth is different than when plumbed and measured is due to the location difference. However this does not explain why the bottom of the buoy measured 122 ft deep during installation and 150 ft deep the next day. This is due to the stretch of the Kevlar while supporting the 9,600 lb weight less the 4,200 lb buoyancy from the float holding up the array. At 1% stretch, this amounts to 26 feet which is close to the 28 ft observed.

4.0 RECOMMENDATIONS FOR FUTURE SSRNM INSTALLATIONS

- 1. All components should be assembled and pressure tested and electronically tested prior to installation operations. The strength member should be marked for hydrophone locations not just length indications.
- 2. All components should be designed to take installation loads not just installed loads.
- 3. When depth is as critical as the specifications stated, a better method of placing the array at the desired depth should be developed. This may require a redesign of the array itself, such as using a two-point spread moor rather than the single point moor that was installed.



·:

Figure 3.1 - SSRNM Termination Device

- 4. For all ocean operations, have spares for everything, especially small pieces that are being handled over the side of the vessel.
- 5. Mark length of electrical cable (every 100 ft).
- 6. The array electrical cable length should incorporate a given percentage of slack in order to accommodate a tension free connection to the mechanical cable.
- 7. Mark length of shore cable (every 1000 ft or .1 NM).
- 8. Reduce in-air weight/size of clump to make installation handling easier.

) [